


PLAN
SCALE: 1"=40'



EXIST. WELL

#35 CHUCK HOLLOW ROAD
MAP 75 PARCEL 105
THOMAS F. CARROLL

#37 CHUCK HOLLOW ROAD
MAP 75 PARCEL 108
DAVID G. STANLEY-BROWN, TR
THE WINDMOOR NOMINEE TRUST

#38 CHUCK HOLLOW ROAD
MAP 75 PARCEL 66.1
CHARLES F. SNOW
(VACANT)

#7 PARSONS LANE
MAP 75 PARCEL 107
JOSEPH J. & LINDA D. HALE, JR.

EXIST. WELL

CHUCK HOLLOW ROAD
(50' WIDE)

EXISTING SOIL ABSORPTION SYSTEM
2 - QUICK4 INFILTRATOR TRENCHES
2.8'W x 38.4'L x 16"H EACH

#40 CHUCK HOLLOW ROAD
MAP 75 PARCEL 65.2
ARTHUR I. READE, JR., TR.
(VACANT)

#41 CHUCK HOLLOW ROAD
MAP 75 PARCEL 110
GILBERT & DEBORAH RENAUT
(VACANT)

MAP 75
PARCEL 109
65,788± S.F.
(1.51 ACRES)

CLEANOUT
EXISTING GARAGE SLAB
EXISTING HOUSE
EXISTING 1500 GALLON SEPTIC TANK
EXISTING CLEANOUTS (TYP.)
EXIST. WELL
APPROXIMATE GROUNDWATER FLOW

INVERT SCHEDULE

T.O.F.	101.14
INVERT OUT FOUND.	99.24
INVERT IN SEP. TANK	97.20
INVERT OUT SEP. TANK	96.99
INVERT IN C. BOX	87.25
INVERT OUT D. BOX	86.98
INVERT INTO TRENCHES	86.91
BOTTOM S.A.S.	85.90

TIES TO COMPONENTS

	A	B	C	DESCRIPTION
1	30.5'	23.7'	-	TANK COVER IN
2	27.6'	27.1'	-	TANK COVER CENTER
3	24.9'	30.8'	-	TANK COVER OUT
4	145.3'	-	180.6'	D-BOX
5	141.1'	-	174.0'	END CENTERLINE INFILTRATORS
6	127.6'	-	148.8'	END CENTERLINE INFILTRATORS
7	148.7'	-	180.0'	END CENTERLINE INFILTRATORS
7	135.9'	-	155.8'	END CENTERLINE INFILTRATORS

SITE BENCHMARK:
GARAGE SLAB
ELEVATION=100.0(ASSUMED)



TO THE TOWN OF NANTUCKET:

"I CERTIFY THAT THE SEPTIC SYSTEM HAS BEEN CONSTRUCTED IN ACCORDANCE WITH THE TERMS OF THE PERMIT AND THE APPROVED DESIGN PLAN AND MEETS THE REQUIREMENTS OF THE TOWN AND STATE REGULATIONS, AS-BUILT".

DONALD F. BRACKEN, JR. P.E.

INSTALLER

Prepared By:

BRACKEN ENGINEERING, INC. Engineering - Surveying
Environmental Permitting

19 Old South Road, P.O. Box 3525
Nantucket, MA 02584
Phone: 508-325-0044 Fax: 508-833-2282

SEPTIC AS-BUILT
IN
NANTUCKET, MA

Prepared For:
DAVID G. STANLEY-BROWN
#39 CHUCK HOLLOW ROAD
MAP 75 PARCEL 109

Date: FEBRUARY 11, 2008 Scale: 1" = 40'
Drawn By: JRL Checked By: DFB Job No.: 406-01
Drawing Name: 39 Chuck Hollow-SAB.dwg